
Mt. Washington Landslide, Emergency Response, and Wall Design



Trey Walker, PE







Overview

- Introduction
- Landslide Review
- Emergency Response Activities
- Site Investigation & Assessment
- Retaining Wall Design
- Retaining Wall Construction
- Survey Monitoring
- Summary & Lessons Learned

(Charles Bertram - Lexington Herald Ledger)



Site Location & Information

- ► Landslide Occurred on April 8, 2014 ≈ 3:00am
- Affected Parties
 - Norfolk Southern Railway
 - City of Pittsburgh
 - Duquesne Incline
 - LeMont Restaurant
 - Other Residents




amec foster wheeler

Introductory Videos





Introductory Videos





Landslide Statistics/Impacts

- ► Total Slide
 - 350-feet by 600-feet Slide Mass
 - Estimated 450,000 CY
 - Initiated ≈ 500-feet upslope of track



- Norfolk Southern
 - Double Mainline Tracks Covered in Debris
 - ▶ 75' stretch of Main Track #1
 - ▶ 230' stretch of Main Track #2
 - ▶ Up to 15' deep



(Darrell Sapp – Pittsburgh Post-Gazette)



Emergency Response Activities

- Objective: Safely Restore
 Freight Operations
- Remove Debris & Restore Traffic on Main Track #1
- Remove Debris & Restore Traffic on Main Track #2
- Total of 3,000 CY Removed from Track
- Continue Observation of Slide Mass
- Begin Site Assessment & Investigation



(Darrell Sapp – Pittsburgh Post-Gazette)



Site Investigation & Assessment

Site Investigation:

- Walk accessible sections of slope and slide mass.
- Geotechnical Borings
 - 4 total
 - 3 at track Level, 1 on slide mass.
- Survey of lower slope

Assessment:

- Colluvial soils
- Wet Conditions
 - Fluctuating groundwater conditions
 - Abnormally cold winter
- Slide toe located at track level
- Embankment supporting track is not moving

amec foster wheeler

Retaining Wall Design

- ► Objectives:
 - Protect track operations
 - Provide a system with advanced warning of additional movement



- Multi-phase approach
 - Provide design for immediate protection (Phase 1)
 - Continue to monitor slope conditions
 - Provide design for alternate reinforcement (Phase 2)
- Design timeline
 - Conceptual design in 5 days
 - Preliminary design in 10 days
 - Owner & Contractor review
 - Final documents/begin construction in 20 days
 - Phase 2 design in 6 weeks




- Design Concept Phase 1
 - Soldier Pile Wall
 - 12' typical design height
 - 6' stickup above stone backfill
 - 355' wall length
 - HP14x117 Soldier Pile (60' Length)
 - 24" diameter socket
 - Backfilled with concrete
 - HP12x53 Continuous Waler
 - Precast Concrete Lagging
- Design Concept Phase 2
 - 225-kip Anchors
 - 2 anchors every other bay
 - Double HP waler connected to wall face

- Benefits of design
 - Meets objectives
 - Small footprint
 - Easily altered alignment
 - Short construction timeline
 - Phase 1 easily adapted to incorporate phase 2




Wall Alignment






Phase 1 Typical Section





Phase 2 Typical Section



Retaining Wall Construction




Construction Notes

- Wall Alignment changed to expedite construction and accommodate utilities
- Some lagging sections were cast-in-place
- Grading upslope of wall to assist drainage
- Construction completed within one month.






Construction Photos





Survey Monitoring

- Monitoring Program
 - Movement monitored for 12 weeks after completion.
 - Final readings August 2014
 - 27 monitoring points along top of wall
 - Max movement ≤ 0.25"
 - As result Phase 2 was not constructed





Summary and Lessons Learned

- Revisit Objectives
 - Protect track operations
 - Provide a system with advanced warning of additional movement
- Design and Construction complete within two months
- Wall Monitored for Movement
 - Minimal movement observed over three months
- Phase 2 Not Constructed
 - Saved approximately \$400,000 in construction costs.

- Lessons Learned
 - Comfortable with limited information & changing conditions
 - Provide flexible designs





Questions?

Contact Information: Trey Walker, PE trey.walker@amecfw.com